

Lobo Lane Paving and Drainage Improvements

Little Elm, Texas

CobbFendley is the Civil Engineer for this Paving and Drainage Improvement project that includes replacing approximately 5,000 linear feet of a two-lane asphalt rural section with a concrete curb and gutter section and underground storm sewer. Paving improvements planned are a four-lane, 49-foot section south of Eldorado Parkway as part of TxDOT's FM 720 improvements project, a two-lane, 31-foot section to Cottonwood Ballpark. A two-lane, 27-foot section leading into Little Elm Park is planned north of Eldorado Parkway. These sections will include underground storm sewer, an eight foot hike and bike trail, water, sanitary sewer, lighting, landscape, and irrigation improvements. In addition to engineering design services, this project required close coordination with TxDOT and the U.S. Army Corps of Engineers.



Project Length:

1 mile

Services:

Survey Verification

Grant Coordination

Engineering Design

Bid Coordination

Construction Administration

Record Drawing Preparation

Construction Cost:

\$6 Million

Completion Date:

Currently under construction