

Kirby Drive – Overhead to Underground Houston, Texas

This project involved relocating aerial utilities from existing poles to new underground locations. Utilities involved on this project include CenterPoint Electric, AT&T-Texas, Comcast, Phonoscope, TVMax, AT&T Legacy, and Time Warner. CobbFendley met with each utility company to obtain information for lines that required relocation, which included the number of ducts, number of handholes, and the location of handholes. Once all information was acquired, relocations were designed to place joint trench conduit duct banks for telecommunications, cable TV, and City of Houston traffic signal cable. A layout of the CenterPoint conduit was acquired from CenterPoint Power and plans were designed for relocation of the power distribution lines. The plans and construction cost estimates were included in the roadway reconstruction plans. During the construction phase, CobbFendley reviewed and approved shop drawings, answered any change order requests, attended bi-weekly progress meetings, and assisted during the construction of the duct banks.

Project Limits:

Kirby Drive from Richmond Avenue to Westheimer Road

Completion Date:

March 2009

